

February 7, 2025

Posted via Ariba
(1 pages)

**ADDENDUM No. 3
REQUEST FOR TENDER No. Doc4897137822
CONTRACT No. 25TW-CPI-02CWD**

SUBMISSION DEADLINE: 12:00 NOON (LOCAL TIME), FEBRUARY 24, 2025

**FOR: FULL LENGTH TRENCHLESS REHABILITATION OF EXISTING GRAVITY SEWERS
AND RELATED WORKS AT VARIOUS LOCATIONS (ETOBICOKE SOUTH)**

Please refer to the above Request for Tender document in your possession and be advised of the following:

I. QUESTIONS AND ANSWERS

Q1. Regarding the priority repairs mentioned in the repair list appendix 1, could you confirm if the 8 sections that have Complete work outside of July-Nov 2025 window, shall be done before July or after November 2025 considering the 100 working days for interim completion.

A1. The 8 sections (SL2004878, SL2113892, SL2113893, SL2113904, SL2113939, SL2114041, SL2114043, SL2114182) shall be completed prior to July 1, 2025 due to construction conflict with Toronto Hydro Underground & Overhead Electrical Work in the corresponding areas.

Q2. Would you please confirm for testing CIPP liner samples as per TS 465.08.02, shall we also consider resin analysis test and whether these tests shall be done per each CIPP shot or in another arrangement?

A2. Contractor shall note that TS 465 is for lining of sewer services (i.e. lateral connections). TS 4.10 (February 2024) is for the full-length lining of sewers. There is no scope in this tender associated with lining of sewer services. For full-length CIPP lining, tests shall be performed per each CIPP shot.

Q3. Would you consider specifying and mandating the use of VeriCure for temperature monitoring of the CIPP lining as part of the QA/QC process?

A3. The City will not accept or deny any specific temperature monitoring system at this stage. The Contractor must employ a continuous temperature monitoring system compatible with their proposed lining system that is capable of recording temperature along the entire length of the pipe as part of its CIPP curing process. Contractor shall refer to TS 4.10.28.7 regarding continuous temperature monitoring requirements.

Q4. Would you consider Quadex I&I Guard SSF | 4 as an approved soil stabilization grout for this project?

A4. The City will not accept or deny any product at this stage. Contractor shall use appropriate grouting material compatible with its own means of installation according to Part 3 specifications.

Should you have any questions regarding this addendum send via the event message board or contact Donna Landrito at donna.landrito@toronto.ca.

Suppliers must acknowledge receipt of all addenda in the space provided on Part 4 – Submission Form as per Part 1 Tender Process, Section 1 RFT Specific Process and Submission Instructions, Item 1.7 – Addenda, of the Tender document. All other aspects of the Tender remain the same.

Yours truly,

Marianne Gonzalez-Angulo, Supervisor
Infrastructure and Development Services
Purchasing Client Services
Purchasing & Materials Management Division